

9. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

No.	Particulars of work	Per	Quantity
1	Dismantling brick in mortar wall	C. ft.	1,981
2	Removing teakwood joists	No.	22
3	Removing doors and windows	No.	8
4	Do stone slabs	C. ft.	77
5	Lowering the basement and surrounding of Guard room including carting	C. yd.	92
6	Carting	Carts	176
7	Dismantling the Fort wall including brick masonry, stone facing and carting	C. yd.	1,395
8	Earthwork excavation	C. ft.	111
9	Do for filling including carting	C. ft.	6
10	Concrete in chunam	C. ft.	779
11	Burnt brick in chunam foundation, basement and superstructure	C. ft.	10,517
12	Do do arch work	C. ft.	312
13	Burnt stone slabs 6" thick highly dressed	S. ft.	234
14	Plastering with chunam with 2 coats finely finished	Sqr.	99'23
15	White and colourwashing	Sqr.	99'23
16	Teakwood windows with panel shutters and iron bars, fixing, hinges, etc., complete	S. ft.	512
17	Teakwood glazed fanlights, complete	Sqr.	100
18	Pukka terracing	Sqr.	22'06
19	Cornice with string course, complete	R. ft.	226
20	Stone brackets, with Cuddapah slab lovel projection plastered over complete	No.	36
21	Stone brackets, large, in front of entrance	No.	2
22	Brick masonry parapet ornamental with plastering top cornice, etc., complete	R. ft.	215
23	Masonry finial or kiosk over front pillars	No.	3
24	Masonry prabhavali with ornamental work as per elevation	No.	1
25	Ornamental work for front pillars	Lump sum	17
26	Masonry finials	Cwt.	35
27	Steel girders including hoisting, painting Ry. freight, etc., complete	C. ft.	218'50
28	Teakwood work wrought and put up	Sqr.	12'24
29	Silicate painting	Sqr.	21'25
30	Wood oiling	C. ft.	2,040
31	Stone flagging with mortar, pointing using old stones	S. ft.	193
32	Teakwood ornamental gate	No.	
<i>Dismantling the Band room.</i>			
1	Dismantling the heavy masonry walls of Janasala	C. ft.	33,842
2	Do brick in mortar walls including boulders	No.	11,609
3	Removing teakwood joists	No.	69
4	Removing and stocking the doors	No.	8
5	Do do windows	No.	2
6	Do couples of car shed	No.	31
7	Do the thick reapers of zinc roof	R. ft.	924
8	Do the zinc sheet roof	Sqr.	25'34
9	Earthwork excavation and carting, including dismantling of foundation masonry	C. yd.	365
10	Carting	Cart	3,226

GURU RAO SIRSI,
Assistant Engineer.

MYSORE DIVISION.

NOTICE.

The attention of the public is invited to advertisement in detail published in the *Mysore Gazette* dated 7th February 1918, calling tenders for "Restoring Homma tank, Register No. 36 of Chamrajnagar Taluk."

P. SUBBA RAO,

For Executive Engineer.

HASSAN DIVISION.

Dated 2nd February 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to the 7th March 1918, for constructing an additional block to the A. V. School at Arkalgud. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of the 30th June 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing an additional block to the A. V. School at Arkalgud," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

18. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the approximate quantities of work for constructing an additional block to A. V. School at Arkalgud.

No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in basement	C. yd.	99
2	Concrete	C. ft.	795
3	Burnt brick or stone in mortar, foundation and basement	"	2,363
4	Burnt brick in mortar superstructure	"	767
5	Burnt brick in clay do	"	3,070
6	Burnt stone slabs, dressed	S. ft.	539
7	Burnt brick in mortar, arch work	C. ft.	45
8	Teakwood panelled doors with iron fastenings, etc., complete	S. ft.	263
9	Teakwood windows with glazed and panelled shutters, iron bars, etc., complete	"	234
10	Teakwood work with oiling, etc.	C. ft.	163'20
11	Roofing with 1st class Mangalore tiles on teak reapers, etc.	Sq.	34'50
12	Ridge tiles set in mortar	R. ft.	140
13	Zinc sheets for valley	S. ft.	192
14	Teakwood plank	"	192
15	Chunam border	R. ft.	83
16	Teakwood eave board	"	304
17	Chunam plastering	Sq.	79'00
18	White and colour washing	"	79'00
19	Flooring with Cuddappah or Mangalore tiles on 8" concrete bed and cement pointing.	"	20'43
20	Painting	"	16'98
21	Moulding works to big windows of side room as per plan	Lump sum	
22	Tarring to wood work	"	
23	Curving corners of rooms	"	
24	Cutting grooves to pillars	No.	8
25	Mangalore ventilating tiles	"	18
26	Clearing site, etc.	Lump sum	

Notice dated 10th February 1918.

The following sums are outstanding as arrears due to the contractors who had worked in the Hassan Division and whose whereabouts are not known. Such of the amounts as are not claimed within three months from the date of issue of this notice will be credited to Government.

Statement showing the arrears due to contractors whose whereabouts are not known.

No.	Name of work	Name of contractor	Period from which the amount is outstanding	Amount	Remarks
1	Opening out a feeder channel to Heragu Urumundinakere tank.	Govindasami Mudaliar	June 1913	Rs. a. p. 0 15 6	
2	A. R. of Chaugaravalli channel	Thimmaiya	June 1915	8 5 9	
3	Improving the drainage on Bangalore-Mangalore road.	Ibrahimberry	February 1914	2 8 0	
		H. Mallegowda	July 1914	1 4 4	
		Madanai	April 1914	1 11 0	
4	In old Kadur channel	Venkatesiah		3 13 3	
5	A. R. of Bangalore-Mangalore road	H. Balegowda		2 1 0	
		Gavigowda		3 12 2	
		Thimmegowda		9 3 5	
		Buden Beg	July 1915	1 5 0	
		Poorthanerry		20 1 0	
6	A. R. of Kattaya-Hallibyle road	Krishnegowda	February 1913	4 13 4	
		Lakshmegowda		12 10 0	
7	A. R. of Anemahal-Mudgere road	Nazaiya	March 1915	7 0 10	
		Puttaswamigowda	December 1915	1 12 0	
8	A. R. of Vanagur-Mallipatna road	Hirianna	November 1915	13 2 0	
9	A. R. of Arsikere-Channarayapatna road.	Channaiyah	1915-16	0 8 0	
		Kalaiah	Do	3 0 0	
10	A. R. of Arsikere-Hassan road	Junigowda	1915-16	4 13 0	
		Sidda	Do	0 9 1	
		Chikkagowda	April 1916	14 11 0	
11	A. R. of Banavar-Belur-Mudgere road.	Venkatanarasappa	July 1915	12 8 0	
		Thimmaboyi		5 13 4	
		Devaraju		3 2 4	
		P. Shamanna		11 7 0	
		Mahomed Oosman		1 11 0	
		Munisami		0 4 6	
		Samanna		1 2 6	
		Puttaiya		3 5 10	
		Thimmarayappa		1 10 2	
		Ramabhatta		2 4 10	
		Baramoji		2 8 3	
12	A. R. of Banavasi-Yesurpet road.	Kenchamma		3 13 2	
		B. Nirvani		3 8 0	
13	A. R. of Sukravarasante-Subramanya road.	S. Puttegowda		1 5 0	
14	A. R. of Manjarabad-Kodlipet road	S. Puttegowda		1 3 0	
15	A. R. of Saklespur-Arehalli-Chikahalli road			0 13 4	
16	A. R. of Arehalli-Bekkodde road	Khader Hussain		1 14 0	
		Mahomed Hussain		3 6 2	
		Ranga Buyi		0 0 2	

R. W. SCALDWELL,
Executive Engineer.